

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 412 Union National Bank Bldg, Wichita, Kansas.

17-24-130 KOTTED
 J.E. Jamison

STANOLIND OIL & GAS CO.
 Robert Semon Shank No. 1

SEC. 17 T. 24 R. 13W.
 SE SE SE
 330' N of S.L. 2310' E of WL.

Total Depth. 4145
 Comm. 10-13-37 Comp. 11-3-37
 Shot or Treated.
 Contractor.
 Issued. 12-4-37


County Stafford.

DEC 4 1937

Rotary

CASING.

103/4" 251'



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations

sand	132	Top siliceous by	
sand and shale	235	Schlumberger test	4117
red rock	253	Total Depth	4145
red bed	990		
shale	1650		
lime	1675	Siliceous lime	4117-4145
shale	1710	Top Viola lime	4025
lime	2028	Simpson sand	4070
broken lime	2118		
lime	2410		
broken lime	2810		
lime	2935		
broken lime	3000		
lime	3510		
shale	3600		
lime	3650		
shale	3652		
lime	3915		
red rock	3920		
shale	3940		
lime	3977		
shale	4026		
lime	4070		
Simpson sand	4071		
shale	4109		

Core # 1. 3'18" Recovery.
 chert white oolitic with
 sdy green shale SSO 4110
 dolomite sdy tan to white
 with green shale inclusion
 no show of oil 4117
 core # 2 6"/13" Rec.
 dolomite sdy tan to
 green 4119
 shale green 4121
 dolomite white to tan
 cryst. porous SSO in
 samples 4130
 Core # 3 /15" Rec.
 Dolomite wh to tan. some
 porosity no show 4145