

18-24-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Engle No. 1
ENGLE

SEC. 18 T. 24 R.13W
NW NW SE

Total Depth. 4240'
Comm. 8-18-60 Comp. 8-29-60
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 1-7-61

County Stafford
KANSAS



Elevation. 1934' KB

Production. 25 BOPD

CASING:

8 5/8" 418' cem w/275 sx.
5 1/2" 4235' cem w/200 sx.

Figures indicate Bottom of Formations.

surface clay & sand	100
clay, shells & shale	220
red bed	285
clay, shale & shells	310
sand	390
red bed	418
red bed & sand	985
sand, shale & salt	1640
sand, shale & shells	1700
lime & shale	1825
shale & lime	1930
lime & shale	2105
shale	2145
sand	2160
shale & lime	2360
lime & shale	3470
shale & lime	3615
lime	3969
chert	4059
lime & shale	4093
lime	4132
shale	4165
shale & sand	4197
lime	4240
Total Depth	

TOPS:

Heebner	3447
Toronto	3468
Douglas	3486
Brown Lime	3584
Lansing	3614
Mississippi	3974
Kinderhook	4012
Viola	4074
Simpson	4130
Simpson Sand	4146
Arbuckle	4190

DST 3975-94', op 30 min, GTS/3 min, TSTM
sprayed mud in 18 min, fl. oil in 20 min.
Rec. out full str. oil Rec. 120' heavy
oil cut muddy water. IBHP 1315#/20 min,
FBHP 1315#/30 min, FP 445#-945#.