


18-24-13W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO.  
Farm- Harrison No. 5

SEC. 18 T. 24 R. 13W  
SE SW NW

Total Depth. 4101'  
Comm. 9-6-60 Comp. 9-17-60  
Shot or Treated.  
Contractor.  
Issued. 1-14-61

County Stafford  
KANSAS  


CASING:  
10 3/4" 215' cem w/180 sx.  
7" 4101' cem w/125 sx latex 600 gallons

Elevation. 1930' DF  
Production. 195 BOPD

Figures indicate Bottom of Formations.

surface clay & sand	30
sand	120
shale	215
red bed	300
sand	335
red bed	827
Anhydrite	845
shale & shells	1850
shale & lime	1895
lime & shale	1925
lime	2080
lime & shale	2355
broken lime	2510
lime & shale	2770
shale & shells	2875
lime	2950
lime & shale	3140
lime	3265
lime & shale (some chalky)	3330
lime	3449
shale	3456
lime	3460
lime & shale	3487
shale	3584
Brown lime	3615
Lansing lime	3875
lime & shale	3940
Conglomerate	3961
Mississippi	3980
chert	3988
shale	4047
Viola	4060
chert	4101 RTD
Total Depth	

TOPS:	SAMPLE	SCLUMBERGER
Heebner	3450	3448
Toronto	3472	3469
Douglas	3487	3486
Brown Lime	3585	3584
Lansing	3616	3614
Base Kansas City	3879	3874
Conglomerate	3943	3940
Mississippian	3961	3939
Kinderhook Shale	3938	3986
Viola	4047	4045

DST #1 3963-3980', op 1 hr, weak steady blow thruout, rec. 65' very slightly oil & gas cut mud ISIP 105#/30 min, FSIP 100#, /30 min, IFP 0#, FFP 0#.

DST #2 4049-4060', op 1 hr, strong blow thruout, rec. 60' muddy gassy oil, 90' heavily oil & gas cut mud. No water ISIP 825#/30 min, FSIP 420#/30 min, IFP 0#, FFP 95#.