

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg, Wichita, Kansas.


LAUCK-MONCRIEF, CONTINENTAL OIL CO. &  
CITIES SERVICE OIL CO.

SEC. 18 T. 24 R. 13W  
SW<sub>6</sub> SW

McConnaughty No. 1

County Stafford.

Total Depth. 4234 P. B. 3902  
Comm. 3-24-39 Comp. 5-7-39  
Shot or treated. 1000 gal.  
Contractor  
Issued. 6-17-39



CASING.

13" 360'  
10" 814'  
7" 3902'

Elevation.

Production. DRY

Figures Indicate Bottom of Formations.

surface	18	lime	3480
sand and clay	110	shale	3492
shale	130	lime	3500
shale and shells	365	lime and shale	3575
lime shells	370	lime	3588
shale and red rock	422	shale	3591
lime shells	430	lime	3855
shale	460	broken lime	3880
red rock	580	lime	3904
red rock and shale	729	lime and shale	3920
shale shells and		shale	3924
rod rock	790	conglomerate	3943
Artosian water 730		shale	3950
rod rock	798	lime	3957
anhydrite	839	shale	3990
rod rock and shale	920	shale and chert	4020
rod rock shale and gyp		lime and chert	4055
shells	1045	lime and shale	4065
rod rock and lime shells	1125	lime	4079
shale and shells	1240	lime and chert	4098
shale and salt	1370	lime	4125
shale	1450	shale	4135
salt	1465	lime	4157
salt and shale	1675	shale	4175
shale and shells	1820	sand and shale	4203
broken lime	1890	shale	4211
lime	1940	lime	4234
broken lime	1985	Total Depth	
shale and lime	2010	P.B. 3902	
broken lime	2020	Tops Dorrick Floor:	
shaly lime and shale	2120	Top Lansing	3590
shale shaly	2160	Top Viola	4018
lime	2200	Top Simpson	4156
lime and shale	2233	Top Arbuckle	4210
shale	2270		
shale and shells	2300	conert	3850
broken lime	2345	ripped casing	3822-26 Rainbow
shale and shells	2390	Perforated casing	
broken lime	2500	<del>3822-26</del> 10 shots Rainbow.	
shale	2540	3802-11 10 shots.	
broken lime	2640	3745-53 10 shots $\frac{1}{2}$ BW 1 hr 20 Min.	
shale	2730	Rainbow Oil	
broken lime	2755		
shale	2860	3730-33- 4 shots.	
broken lime	2900	3672-84 16 shots.	
shale	2920	3662-65 3 shots.	
lime	2929	3626-34 7 shots show gas	
shale	2948		
lime and shale	2975	Test- 2-3 bbls water per hr	
lime	3065	show oil and gas.	
broken lime	3110		
shale	3160	acidized with 1000 gal.	
broken lime	3175	3000' water very slight show oil	
lime	3444	in 12 hours.	
lime and shale	3470		