

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


18-24-13W

Company. NATURAL GAS & OIL CO.
 Farm- McConnaughay No. 4

SEC. 18 T. 24 R.13W
 SW NE SW

Total Depth. 4177'
 Comm. 1-27-61 Comp. 2-5-61
 Shot or Treated.
 Contractor. Strata Drlg.
 Issued. 6-3-61

County Stafford
 KANSAS



Elevation. 1931' RB

CASING:
 8 5/8" 239' cem w/230 sx.
 4 1/2" 4027' cem w/150 sx.

Production. 35 BOPD
 3,310,000 CFG

Figures indicate Bottom of Formations.

sand	120
shale & shells	240
red bed & shale	1250
shale & shells	1700
shale & lime	2390
shale	2585
shale w/lime strks	2885
lime & shale	2997
lime	3676
lime & shale	3956
shale	3972
lime & shale	4054
lime & shale chert	4081
cherty lime	4094
chert, lime & shale	4124
lime & shale	4175 RTD
lime	4177
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Heebner Shale	3436	3437
Brown Lime	3570	3572
Lansing-Kansas City	3601	3601
Base Kansas City	3856	3856
Mississippian	3908	3910
Kinderhook	3954	3956
Viola	4024	4024
Simpson Shale	4143	4145
Simpson Sand	4162	4162