

18-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Rixon "A" No. 2

SEC. 18 T. 24 R.13W
NE SW NE

Total Depth. 4278'
Comm. 7-26-61 Comp. 8-8-61
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 12-30-61

County Stafford
KANSAS



Elevation. 1928' DF

Production. 65 BOPD

CASING:

10 3/4" 252' cem w/375 sx.
7" 4183' cem w/125 sx.

Figures Indicate Bottom of Formations.

sand	160
blue shale	252
shale	257
red bed & sand	823
shale & lime	835
shale & red bed	880
Anhydrite	910
shale & shells	1750
shale & lime	2030
lime & shale	2240
lime, shells & shale	2370
lime & shale	2710
shale	2825
lime & shale	3619
shale & lime	3695
lime	3760
chalky lime	3800
lime	3925
lime & shale	3970
chert	3990
lime & chert	4050
lime	4142
lime & shale	4255
lime	4278
Total Depth	

TOPS: LOG

Heebner	3448
Toronto	3466
Douglas	3486
Brown Lime	3583
Lansing	3614
Base Kansas City (scout)	3869
Mississippian	3970
Viola	4073
Simpson	4120
Simpson Sand	4135
Arbuckle (Sample)	4178

DST 3971-90', op 1 hr 10 mins, rec. 540'
~~gas in pipe, 50' GCM, All pressures zero.~~

DST 3925-4050' op 1 hr 10 mins, rec. 30'
mud w/few specks oil, 120' mud. IBHP 780#/30 min,
FBHP 690#/30 min, FP 60#-140#.

DST 4110-4142', op 1 hr 10 mins, rec. 450'
gas in pipe, 150' heavy O&GCM. IBHP 1410#/30
mins, FBHP 1070#/30 mins. FP 0#-0#.