

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


19-24-13W

Company- D. R. LAUCK OIL CO.
Farm- Toland No. 1

SEC. 19 T. 24 R. 13W
SE NW NW

Total Depth. 4100'
Comm. 6-1-61 Comp. 6-11-61
Shot or Treated.
Contractor.
Issued. 9-2-61

County Stafford
KANSAS



CASING:
8 5/8" 223' cem w/180 sx.

Elevation. 1935' DF

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	15
sand	128
shale	223
red bed	305
sand	330
red bed	325
Anhydrite	855
red bed & shells	1045
red bed & shale	1200
shale & shells	1695
lime & shale	1905
lime	2035
lime & shale	2180
shale & lime	2400
shale & shells	2555
shale & lime	3050
lime & shale	3140
shale & lime	3270
lime & shale	3395
lime	3461
Heebner	3466
lime	3470
shale & lime	3630
lime	3978
lime & shale	3987
Mississippi	3998
chert, lime, shale	4018
shale & chert	4100 RTD
Total Depth	

TOPS:	SAMPLE	WELEX
Heebner	3461	3454
Toronto	3482	3480
Brown Lime	3599	3598
Lansing-Kansas City	3631	3630
Base Kansas City		3872
Mississippian	3987	3986
Kinderhook	4016	4018
Viola	4077	4076

DST #1 3988-3998', op 30 mins, weak blow
10 min. & died. Rec. 10' drilling mud.
ISIP 200#/15 min, FSIP 0#/30 min,
FP 0/0#.

DST #2 3998-4018', op 1 hr, weak blow
thruout, rec. 130' watery mud. ISIP 1440#/30 min.
FSIP 1360#/30 min.