


Company - CONTINENTAL OIL CO.
Farm - H.V. Elwell No. 1.

23-24-13W
SEC. 23 T. 24 R. 13W
NWc NE
3 30'S 330'E N $\frac{1}{4}$ Cor.

Total Depth. 4126' GL
Comm. 10-19-44 Comp. 11-11-44
Shot or Treated.
Contractor.
Issued. 12-9-44

County. Stafford
KANSAS



CASING:
10 $\frac{3}{4}$ " 446' Cem.

Elevation. _____

Production. Dry

Figures indicate Bottom of Formations.

| | |
|------------------|-------|
| sand | 0-145 |
| shale & shells | 600 |
| shale & red bed | 745 |
| anhydrite | 770 |
| shale & shells | 1705 |
| lime | 1900 |
| sand | 1955 |
| sand & lime | 2020 |
| lime | 2185 |
| lime sdy & shale | 2285 |
| lime brkn | 2464 |
| lime & shale | 2785 |
| lime | 3035 |
| shale & shells | 3620 |
| lime | 3885 |
| lime & chert | 3984 |
| chert | 4010 |
| lime & chert | 4079 |
| lime & shale | 4100 |
| shale | 4117 |
| lime & shale | 4126 |
| Total Depth | GL |

Top of Arbuckle Lime 4117

11-9-44 Drilled to a TD of
4126 in Arbuckle Lime; ran
drill stem test w/packer
set @ 4118; tool open 30
mins; recovered 320' wtr
no oil

11-11-44 Plugged & abd

Total Depth 4126 in Arbuckle Lime

Note: Footages calculated from
ground level