

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


24-24-13W

Company- HUDSON PETROLEUM CO.
Farm- McCune No. 1

SEC. 24 T. 24 R. 13W
C E/2 E/2 NW

Total Depth. 4125'
Comm. 4-14-59 Comp. 4-28-59
Shot or Treated.
Contractor. Chief Drlg.
Issued. 8-1-59

County Stafford
KANSAS



CASING:

8 5/8" 250' cem w/200 sx.
5 1/2" 4123' cem w/150 sx.

Elevation. 1904'

Production. 43 BOPD

Figures Indicate Bottom of Formations.

sand & clay	40
shale & sand	250
shale	280
shale & red bed	345
sand & red bed	445
sand	490
shale & shells	735
Anhydrite	760
sand, shale & shell	1140
shale & shells	1680
shale & lime	2105
lime	2255
lime & shale	2290
shale w/lime	2465
shale & lime	3544
lime	3795
shale & lime	3919
chert & lime	4053
shale & sand	4108
dolomite	4125
Total Depth	

TOPS:

Heebner	3367
Toronto	3336
Brown Lime	3514
Lansing-Kansas City	3544
Base Kansas City	3795
Viola	3919
Simpson	4053
Arbuckle	4108

Perf. 3935-38 w/13 shots (Viola)
no shows oil or water
Perf. 4084-86 w/12 shots (Simpson)
no shows oil or water.
Perf. 3568-74 w/24 shots (Lansing)
Swab 5 bbl. oil per hour/6 hr.
Acidized w/500 gal.
Swab 10 bbl. oil per hr/7 hr.