

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 - 185 - 21076
County Number


State Geological Survey

S. 25 T. 24 S. R. 13 W

Loc. C N2 SE

County STAFFORD

640 Acres



Locate well correctly

Elev.: Gr. 1903

DF KB 1908

Operator
J. A. ALLISON

Address
300 W. Douglas, Suite 305, Wichita, KS 67202

Well No. 4 Lease Name CLINE ESTATE

Footage Location
1980' feet from (N) (S) line 1320 feet from (E) (W) line

Principal Contractor Woodman & Iannitti Geologist Robert E. McCann

Spud Date 8/02/80 Date Completed 9/10/80 Total Depth 3820 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-3/4	8-5/8		307		210	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

DRY HOLE

Operator
J. A. ALLISON

Well No.
4

Lease Name
CLINE ESTATE

S 25 T 24S R 13^{XX}
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1, op 30, si 30; op 60, si 45; weak initial blow increasing to fair (5") throughout, rec. 60' gas in pipe 80' gas cut mud, few specks oil, ISIP 80, FSIP 103, IFP 45, FFP 80.	3566	3593	<u>SAMPLE</u>	<u>TOPS</u>
			Heebner	3380 (-1472)
			Toronto	3395 (-1487)
			Douglas	3415 (-1507)
			Brown Lime	3532 (-1624)
			Lansing	3558 (-1650)
DST #2, op 30, si 30; op 60, si 45 fair blow throughout, rec. 50' gas in pipe, 10' oil cut mud, 60' oil cut watery mud, 120' sl. oil cut muddy water, ISIP 617, FSIP 639, IFP 45, FFP 114.	3621	3641	Base KS City	3813 (-1905)
			RTD	3820 (-1912)
			Log TD	3820
DST #3 op 30, si 30; op 60, si 60; weak to fair blow first open, fair to good blow on 2nd open, rec. 220' gas in pipe, 20' slightly oil cut mud, ISIP 45, FSIP 80, IFP 34, FFP 34.	3685	3705		
DST #4, op 30, si 30; op 60, si 45; good blow throughout, recovered 160' gas in pipe, 80' medium to heavy oil and gas cut mud, 60' medium to heavy oil and gas cut watery mud, 60' slightly oil cut muddy water, ISIP 594, FSIP 650, IFP 45 FFP 103.	3704	3730		
DST #5, op 30, si 30; op 60, si 45; weak blow throughout test, recovered 20' very slightly oil cut thin mud IBHP 126, FBHP 160; IFP 45, FFP 57 RTD 3820', Log TD 3820'. Dry and abandoned.	3793	3820		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. Allison
Signature
Operator
Title
10/9/80
Date

WOODMAN
PHONE 733-0418
PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY

Rotary Drilling Contractors

1008 DOUGLAS BUILDING
104 S. BROADWAY
WICHITA, KANSAS 67202

25-24-13W
60'S, C N/2 SE

September 16, 1980


Company;	J. A. Allison
Farm;	#4 Cline Estate
Location;	C N/2 SE
Section;	25-24S-13W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	September 2, 1980
Compl;	September 11, 1980
Total Depth;	3820'
Casing;	8 5/8 @ 307 w/210 sx.
Production;	D & A

Figures Indicate Bottom Of Formations;

300	Sand & shale
310	Cement
760	Anhy
920	Sand
1675	Shale & lime
2584	Shale & lime
3297	Shale & lime
3593	Lime & shale
3641	Lime & shale
3705	Shale & lime
3770	Lime & shale
3820	Shale & lime

I certify the above to be a true and correct copy of the drillers log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.



K. T. Woodman