

✓
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


25-24-13W

Company- PETROLEUM, INCORPORATED
Farm- Fox No. 1

SEC. 25 T. 24 R. 13W
NE SE SW

Total Depth. 4170'
Comm. 1-5-58 Comp. 1-17-58
Shot or Treated.
Contractor. Garvey Drilling Company
Issued. 3-8-58

County Stafford
KANSAS



CASING:
8 5/8" 280' cem w/250 sx

Elevation. 1909' DF

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	50
shale & sand	740
Anhydrite	750
red bed	1100
shale	1230
shale & shells	1760
lime & shale	2200
shale & shells	2410
shale	2615
shale & lime	3648
lime	3690
Cherty lime	3750
lime	3805
lime & chert	3864
lime	3905
shale & lime	3965
lime & chert	4021
lime	4050
lime & shale	4060
lime	4110
lime & sand	4125
lime & shale	4170
Total Depth	

TOPS: SCOUT	
Anhydrite	750
Heebner	3383
Toronto	3400
Douglas	3418
Brown Lime	3530
Lansing	3554
Conglomerate	3804
Viola	3956
Simpson Shale	4032
Simpson Sand	4088
Arbuckle	4138