


28-24-13W

Total Depth. 4079'
Comm. 1-3-38 Comp. 2-9-38
Shot or Treated. No.
Contractor. Parker Drlg. Co.
Issued. 2-19-38 Rotary w/ cable tool
completion.

FEB 19 1938

County. Stafford



Plotted
J.E.J.

CASING:
13" 419'11"
7" 4072'

Elevation.

Production. Pot. 2063 B.

Figures Indicate Bottom of Formations.

cellar	11	shale blk	3265
clay	35	lime grey	3305
sand & gravel	165	lime & shale	3365
red bed	255	shale	3425
sand	280	lime	3445
red bed	440	shale & lime	3475
sand sft	550	shale grey & strks of	
shale red	780	green shale	3553
anhydrite	800	shale	3557
shale grey	850	lime	3562
shale red & grey	1030	shale	3564
shells	1060	K.C. lime	3608
shale	1220	lime	3635
shale & salt	1260	lime porous, no oil	3649
salt	1301	lime porous sft	3656
salt & shale	1480	lime strks chert	3678
lime	1492	cherty lime hrd	3685
salt & grey shale	1635	lime	3733
shell	1652	lime dense hrd	3737
salt & shale	1679	lime porous sft	3746
brkn anhydrite	1743	lime dense	3749
brkn lime	1872	K.C. lime	3765
shale grey	1895	lime	3768
brkn lime	1980	shale	3778
sand & lime	1995	lime	3797
lime & shale	2023	shale	3804
lime	2045	lime & shale	3851
shale	2075	shale	3855
brkn lime	2100	chert	3865
lime & shale	2123	cherty lime & shale	3880
shale	2135	shale	3905
lime	2212	chert	3922
brkn lime	2240	Viola	3952
shale	2260	lime & chert	4003
brkn lime	2320	lime	4040
shale	2350	shale & sandstone	4064
brkn lime	2385	Simpson	4073
lime	2390	dolomite	4074
shale	2600	lime porous & shale	4075
lime	2620	lime porous	4078
shale	2640	very porous, sat. dol.	4079
lime	2665	Total Depth.	
shale	2710		
shale & shells	2765		
brkn lime & shale	2895		
lime & sticky shale	2930		
shale	2965		
lime	2970		
shale blk	3010		
shale brown	3020		
shale & lime	3040		
lime	3060		
shale & lime	3080		
shale	3110		
shale & lime	3180		
shale blk	3200		
lime sft	3250		
lime white	3255		