

28-24-13 W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NATURAL GAS & OIL COMPANY
Farm- Van Lieu No. 3

SEC. 28 T. 24 R. 13W
C W/2 NW SW

Total Depth. 4179'
Comm. 9-27-57 Comp. 10-13-57
Shot or Treated.
Contractor. Sierra Petroleum Company
Issued. 1-18-58

County Stafford
 KANSAS



CASING:

10 3/4" 293' cem w/200 sx
7 " 4177' cem w/150 sx

Elevation. 1935 KB

Production. 54 BOPD

Figures Indicate Bottom of Formations.

sand & shale	150
shale	600
red bed	835
anhydrite	865
shale & salt	1380
shale & lime streaks	1736
shale & lime	1800
lime	1880
lime & shale	2110
shale	2140
shale & lime	2665
shale	2800
lime & shale	3370
lime	3612
lime & shale	3648
lime	3725
lime chert	3770
lime	3813
lime & chert	3851
lime	3870
lime & shale	3918
shale & chert	4001
lime & shale	4031
chert	4047
chert & shale	4073
lime & chert	4097
shale & lime	4144
lime & chert	4177
arbuckle	4178
arbuckle	4179
Total Depth	

DST: 3755-3770, op 1 hr, good blow, rec.
2045' gas in drill pipe, 15' HO &
GCM, 60' Muddy oil, SI 20 min,
BHP 260%.

Pump test 57 BO, 80% wtr, 24 hrs., wait-
ing on state test.

TOPS: SAMPLE

Anhydrite	835
Heebner	3420
Brown Lime	3557
Lansing	3577
Base Kansas City	3854
Conglomerate chert	3902
Kinderhook	3920
Viola	3984
Simpson	4125
Arbuckle	4176