

30-24-13W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM, INC.
Farm. Harter "E" No. 1

SEC. 30 T. 24 R. 13W
C NW SE

Total Depth. 4245'
Comm. 12-23-61 Comp. 1-7-62
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 6-30-62

County Stafford
KANSAS



Elevation. 1943' DF

Production. 152 BOPD, NW

CASING:

8 5/8" 252' cem w/225 sx.
5 1/2" 4236' cem w/200 sx.

Figures Indicate Bottom of Formations.

sand & gravel	160
red bed & shale	630
red bed	825
Anhydrite	845
shale	1645
shale & lime	1880
lime	2045
shale	2160
lime	2185
lime & shale	2350
lime	2515
lime & shale	2815
shale & lime	3080
shale	3240
lime & shale	3460
shale & lime	3580
lime & shale	3653
lime	3935
lime & shale	3963
lime	3982
chert	4034
chert & lime	4055
chert	4075
chert & lime	4106
chert	4145
chert & lime	4160
shale & sand	4170
shale	4197
sand	4205
lime	4245
Total Depth	

TOPS: SCOUT

Anhydrite	825
Heebner	3463
Brown Lime	3599
Lansing	3626
Base Kansas City	3904
Mississippi	3991
Kinderhook	4044
Viola Chert	4104
Simpson Shale	4176
Simpson Sand	4185
Arbuckle	4230