

32-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. PETROLEUM. INCORPORATED
Farm. Belote No. 2

SEC. 32 T. 24S R.13W
SE SW

Total Depth. 4256'
Comm. 10-27-59 Comp. 11-9-59
Shot or Treated.
Contractor. Garvey Drilling Co.
Issued. 2-6-60

County Stafford
KANSAS



CASING:
8 5/8" 250' w/225 sx.
5 1/2" 4255' w/300 sx.

Elevation. 1952' KB

Production. 200 BOPD

Figures indicate Bottom of Formations.

surface soil & sand	135
sand & gravel	157
shale & red bed	250
red bed	840
shale, salt & shells	1645
shale & shells	1750
lime & shale	1935
lime	2265
lime & shale	2360
shale & lime streaks	2590
shale	2925
shale & lime	3640
lime	3910
lime & shale	3974
lime	4002
shale, lime & chert	4075
lime & shale	4128
cherty lime	4175
lime	4185
shale	4245
shale & lime	4256
Total Depth	

TOPS:	
Heebner	3472
Toronto	3489
Douglas	3507
Brown Lime	3606
Lansing	3635
Base Kansas City	3912
Mississippi	3965
Viola	4054
Simpson shale	4192
Arbuckle	4249