

32-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. ICER ADDIS
Farm. Glasscock "B" No. 1

SEC. 32 T. 24 R. 13W
NW NW SE

Total Depth. 4300'
Comm. 6-16-59 Comp. 6-27-59
Shot or Treated.
Contractor. Chief Drlg. Co.
Issued. 4-8-61

County Stafford
KANSAS



CASING:
8 5/8" 254' cem w/225 sx.

Elevation. 1939' RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	100
sand & shale	250
sand, shale & redbed	467
shale & red bed	800
Anhydrite	810
shale & shells	1730
shale w/lime	1850
lime & shale	1980
lime	2135
lime & shale	2465
shale & lime	2615
shale w/lime	2905
shale & lime	3090
shale & shells	3390
lime & shale	3500
lime	4020
chert	4120
lime	4150
Viola	4210
lime	4260
dolomite	4300 RTD
Total Depth	

TOPS:	
Heebner	3483
Toronto	3503
Brown Lime	3620
Lansing	3649
Base Kansas City	3934
Mississippi	4000
Kinderhook	4129
Viola	4160
Simpson	4242
Arbuckle	4260

DST #1 3779-3845', op 1 hr, rec. 30' mud,
BHP 1195#/30 min.

EST #2 3848-67', op 1 hr, rec. 20' mud,
BHP 385#/30 min.