

33-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company BEARDMORE DRILLING
Farm- Mitchell No. 1

SEC. 33 T. 24 R. 13W
SW NW SE

Total Depth. 4242'
Comm. 5-2-64 Comp. 5-14-64
Shot or Treated.
Contractor. Hellar Drlg.
Issued. 7-4-64

County Stafford
KANSAS



CASING:

Elevation. 1941' KB

8 5/8" 335' cem w/ 275 sx

Production. DRY

Figures Indicate Bottom of Formations.

sand, red bed, shale	341
shale & red bed	799
anhydrite	818
shale & red bed	1750
shale & lime	1980
lime & shale	2171
shale & lime	3300
lime & shale	3638
lime	3703
Lansing Kansas City	3790
lime	3980
shale -chert	4020
Viola	4070
lime & chert	4120
lime	4148
Simpson sand	4170
lime	4202
Arbuckle	4242 RTD
Total Depth	

TOPS: SMP	
Stone Corral anhydrite	799
Base Florence	2160
Topeka	3110
Heebner	3448
Brown limestone	3586
Lansing-Kansas City	3613
Base Kansas City	3892
Mississippian	3939
Kinderhook	3955
Viola	4013
Simpson	4139
Arbuckle	4196

DST # 1 3745-3768
DST # 2 3781-3825
DST # 3 4027-4097
DST # 4 4135-4170