

34-24-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO., INC.
Farm- Halley No. 1

SEC. 34 T. 24 R. 13W
NW NW SW

Total Depth. 4246'
Comm. 2-24-55 Comp. 3-10-55
Shot or Treated.
Contractor.
Issued. 4-16-55

County Stafford
KANSAS



Elevation. 1936' KB

Production. Dry

Figures Indicate Bottom of Formations

sand	160
red rock	550
red bed & shale	1230
shale & shells	1675
lime & shale	1875
lime	1985
lime & shale	3646
lime	3868
lime & shale	4006
chert, lime & shale	4045
chert & lime	4090
chert, lime & shale	4135
sand	4140
shale	4145
Simpson	4170
shale & lime	4201
Arbuckle	4246
Total Depth	

Tops:	
Heebner Shale	3444
Brown Lime	3588
Lansing-Kansas City	3614
Base Kansas City	3873
Shale Conglomerate	3953
Cherty Conglomerate	3976
Viola	4001
Simpson	4136
Arbuckle	4196

DRILL STEM TESTS:

#1 3849-3868', tool open 1 hr., shut in 20 mins. Fair steady blow throughout test. Rec. 62' slightly oil cut mud. BHP 450#.

A Halliburton Radiation-Guard Log was run from 4246' RTD to 316'.