

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Muldick,

Wichita, Kansas


30-24-14W

Company- WESTERN PETROLEUM
Farm- Brown "A" No. 1

SEC. 30 T. 24 R. 14W
SW NE NE

Total Depth. 3624'
Comm. 5-26-63 Comp. 6-9-63
Shot or Treated.
Contractor. Western Petroleum
Issued. 11-2-63

County Stafford
KANSAS



Elevation. 1993 DF

Production. Gas 2, 024,000 CFG

Figures Indicate Bottom of Formations.

sand	125
sand & clay	272
red bed	950
anhydrite	1085
shale	1315
shale, shells & salt	1407
salt & shale	1510
shale & shells	1860
lime & shale	2410
shale & lime	2785
lime & shale	3740
lime	4000
lime & shale	4075
lime	4111
lime & shale	4123
lime & chert	4218
lime & shale	4233
lime & chert	4266
Total Depth	RTD

TOPS: ELECTRIC

Anhydrite	952
Heebner	3580
Iatan	3720
Lansing	3738
Base Kansas City	3996
Mississippi	4130
Kinderhook	4152
Viola	4218

DST# 1 4130-4162' Op 2hrs, strong
blow. GTS in 6 min. Leveled off in
30 min. 627 MCF gas, 20' mud, no water.
IBHP 3160# 30 min; FBHP 1350# 30 min;
IFP 125#; FFP 125#; HH 1880#.