


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- HEIMERICH & PAYNE, INC.
Farm- Koolsch No. 2

SEC. 24 T. 24 R. 14W
NE SW SW
990' N of SL
990' E of WL SW $\frac{1}{4}$

Total Depth. 3890'
Comm. 1-16-53 Comp. 2-1-53
Shot or Treated.
Contractor. Poel Bros. Inc.
Issued. 4-18-53

County Stafford
KANSAS



CASING:

8 5/8" 843' com w/500 sx.
5 1/2" 3889' com w/125 sx.

Elevation. 1944

Production. State Pot. 444 Bbls.
no water.

Figures indicate Bottom of Formations.

sand	65
shale w/sand streaks	195
sand, shale streaks	380
shale, red bed	750
red bed	832
anhyd. chalk	837
anhyd.	863
shale, red bed	910
shale, sholls	1550
shale	1710
shale with anhyd. streaks	1870
shale, sandy limo	2055
limo	2070
shale streaks, limo	2185
limo	2320
shale, limo	3160
limo	3230
limo, shale	3278
limo	3510
shale, limo	3610
limo	3877
limo, shale	3890
Total Depth	

Tops	
Hoebner	3452
Brown Limo	3584
Lansing	3611

2-4-53 3847 $\frac{1}{2}$ - 59 $\frac{1}{2}$ 71 & acidized w/1000 gals.
2-6-53 3774-98 72 Lane Well plug at 3817' & acidized w/500 gals.
2-13-53 3740-47 42 Lane Wells plug at 3758' & acidized w/2000 gals.