


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D. R. LAUCK OIL CO. & SUNRAY MID-CONT.
 Farm- Suiter "B" No. 1 OIL CO.

SEC. 21 T. 24 R. 14W
 NW NW NW

Total Depth. 4303'
 Comm. 4-7-56 Comp. 4-21-56
 Shot or Treated.
 Contractor.
 Issued. 6-30-56

County Stafford
 KANSAS



CASING:

8 5/8" 215' cem w/165 sx
 5 1/2" 4299' cem w/100 sx

Elevation. 1974' DF

Production. 451 BOPD

Figures indicate Bottom of Formations.

clay and sand	155
shale & shells	275
red bed	370
sand & red bed	440
red bed & shale	905
anhydrite	925
shale & shells	1300
salt & shale	1450
shale & shells	1785
lime & shale	2230
lime	2290
lime & shale	3510
lime	3580
lime & shale	3695
lime	3995
lime & shale	4075
chert, lime & shale	4110
chert & shale	4136
chert, lime & shale	4195
chert	4210
chert & shale	4230
chert	4241
shale & sand	4270
shale	4300
Arbuckle	4303 RTD
Total Depth	

Tops:	Sample	Schlumberger
Anhydrite	906	
Heebner	3513	3514
Brown Lime	3656	3654
Lansing-Kansas City	3674	3674
Base Kansas City	3943	3941
Mississippian	4038	4038
Viola	4138	4142
Simpson Shale	4239	4240
Arbuckle	4300	4298

DST #1 3786-3814, open 1 hr; weak blow 1 hr;
 rec. 35' very sli. oil cut mud; IFP O#, FFP O#,
 BHP 90#, in 30 mins.

DST #2 4042-4085'; open 30 min; weak blow 20 min;
 flushed tool; Rec. 20' mud; IFP O#; FFP O#; BHP O#
 in 30 min.