


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRANCIS OIL & GAS, INC.
Farm- Suiter No. 1 A

SEC. 21 T. 24 R. 11W
NW NW NE

Total Depth. 4319'
Comm. 8-2-57 Comp. 8-19-57
Shot or Treated.
Contractor. H-20, Inc.
Issued. 9-28-57

County Stafford
KANSAS



CASING:
8" 230'

Elevation. 1972' DF

Production. Dry

Figures indicate Bottom of Formations.

Top soil-clay	15
sand	75
shale	125
shale-iron strks	230
shale-shells-red bed	340
shale-shells	360
sand	465
red bed	912
Anhydrite	937
shale-shells	1805
shale-lime strks	1855
lime-shale	2025
lime	2100
lime-shale	3749
Kansas City lime	3845
Kansas City lime-shale	3883
Kansas City lime(cherty)	3898
Kansas City lime	3935
Kansas City lime-shale	3960
Cherty lime	3979
lime-shale	4075
chert-shale	4092
lime-shale	4121
chert	4127
chert-shale	4280
Simpson-Arbuckle	4306
Arbuckle	4319
Total Depth	

TOPS:	
Heebner	3528
Brown lime	3668
Lansing	3690
Conglomerate	4058
Kinderhook sand	4084
Viola	4124
Arbuckle	4301