


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION COMPANY
Farm- Bock No. 1

SEC. 17 T. 24 R. 14W
SE SE NE

Total Depth. 4365'
Comm. 11-13-57 Comp. 11-30-57
Shot or Treated.
Contractor. Shelley-Miller Drilling Company
Issued. 2-22-58

County Stafford
KANSAS



CASING:
8 5/8" 215' cem w/150 sx

Elevation. 1985'

Production. Dry

Figures Indicate Bottom of Formations.

surface & sand	82
shale & shells	913
Anhydrite	957
shale & shells	1790
lime & shale	1835
lime	2575
lime & shale	3515
lime	4140
lime & chert	4282
lime	4365- RTD
Total Depth	

TOPS:		
Anhydrite	(Scout)	913
Heebner		3550
Douglas		3590
Brown Lime		3694
Lansing		3716
Base Kansas City		3978
Maquoketa		4100
Kinderhook	(Scout)	4102
Viola	(Scout)	4178
Simpson		4267
Arbuckle		4337

DST #1-4339-48-SI 30", op. 1 hr., wk. blow
thruout, rec. 110' muddy S W.
ISIP -1475; FSIP-1350; FP 15-70.