


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

SUNRAY MID CONTINENT OIL COMPANY
Company- D. R. LAUCK OIL COMPANY, INC.
Farm- Denker No. 1

SEC. 17 T. 24 R. 14W
SE NE SE

Total Depth. 4302'
Comm. 7-17-56 Comp. 7-31-56
Shot or Treated.
Contractor.
Issued. 9-29-56

County Stafford
KANSAS



CASING:
8 5/8" @206' w/165 sx. cem.
5 1/2" @4291' w/125 sx cem.

Elevation. 1982' DE

Production. 455 BOPD

Figures indicate Bottom of Formations.

clay & shale	145
shale & shells	206
shale & shells	
& red bed	315
red bed & shale	900
red bed	910
Anhydrite	932
shale & shells	1270
shale & lime	1770
lime & shale	1845
lime	1955
lime & shale	2454
shale	2460
lime & shale	3662
lime	3945
lime & shale	4065
lime, shale & chert	4165
lime & chert	4205
lime, chert	
& shale	4225
shale & lime	4288
Arbuckle	4292 R.T.D.
Arbuckle	4302
Total Depth	

TOPS:	SAMPLE	SCHLUMBERGER
Anhydrite	910	
Heebner	3519	3520
Douglas	3556	3557
Brown lime	3662	3660
Lansing Kansas City	3681	3682
Base/Kansas City	3945	3947
Kinderhook ?		
Dolomite	4106	4106
Viola	4140	4140
Simpson shale	4232	4233
Simpson sand	4248	4246
Arbuckle	4288	4293

DRILL STEM TESTS:

DST #1 (M-D) 3405-3480, op. 1 hr; strong
blow decreasing to weak blow; rec.
2460' salt wtr. IFP 890# FFP 1350#
BHP 1350# in 30 min.

DST #2 (M-D) 3798-3816, op. 1 hr., good
blow 1 hr. rec. 80' oil cut mud;
IFP 0# FFP 0#: BHP 1240#, 30 min.