


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO., INC. & SUNRAY SEC. 16 T. 24 R. 11W  
Farm- Smith No. 6 MID-CONTINENT OIL NE SE SW  
CO.

Total Depth. 4297'  
Comm. 9-15-56 Comp. 9-28-56  
Shot or Treated.  
Contractor.  
Issued. 11-10-56

County Stafford  
KANSAS



CASING:  
8 5/8" 205' w/165 sx cem.  
5 1/2" 4293' w/125 sx cem.

Elevation. 1980' DF

Production. 356 BOPD

Figures indicate Bottom of Formations

sand-shells	162
shale-shells	205
shale-red bed	380
sand-red bed	485
red bed-shale	915
Anhydrite	935
shale-shells	1785
lime-shale	2060
lime	2140
lime-shale	2875
shale-shells	2905
lime-shale	3385
lime	3460
lime-shale	3560
shale	3660
lime	3943
lime-chert-shale	3990
shale-lime	4030
lime-shale-chert	4185
chert	4210
chert-shale-sand	4240
shale	4291
Arbuckle	4295 RTD
lime	4297

TOPS:	SAMPLE	HAL.
Heebner	3519	3519
Brown lime	3660	3660
Lansing	3680	3680
B/Kansas City	3943	3943
Conglomerate		4058
Viola	4140	4122
Simpson	4232	4234
Arbuckle	4291-	4292

DST #1 - (M-D) 3799-3813, open 1 hr.,  
fair blow 28 min. & died; rec. 30'  
mud w/specks oil; all pressures off  
in 20 min.