


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUMRAY MID-CONTINENT OIL
Farm- H.H. Cotton No. 1

SEC. 16 T. 24 R. 14W
NW NW SE
2260' FSL 2419' FEL SE

Total Depth. 4324'
Comm. 7-18-56 Comp. 7-30-56
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 11-10-56

County Stafford
KANSAS



CASING:
8 5/8" 291' w/300 sx cem.
5 1/2" 4305' w/150 sx cem.

Elevation. 1978'

Production. 449 BO

Figures indicate Bottom of Formations.

sand	60
sand-shale	180
shale-shells	480
sand-shale	830
red bed-shale	917
Anhydrite	950
shale-shells	1900
lime-shale	1985
sdv lime-shale	2090
lime	2220
lime-shale	2360
lime	2 410
lime-shale	3655
lime	4000
lime-shale	4070
lime w/chert	4125
lime-chert	4163
chart	4205
chert-shale	4223
lime-shale	4306
Arbuckle	4306? RTD
Arbuckle	4324
Total Depth	

Tops:
Lansing Kansas City 3684
Mississippi 4069
Viola 4164
Simpson 4244
Arbuckle 4303