


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - JOE MISHLER ETAL  
Farm - Hager No. 1

SEC. 15 T. 24 R. 11W  
NE NE NW

Total Depth. 4272  
Comm. 4-29-50 Comp. 5-14-50  
Shot or Treated.  
Contractor.  
Issued. 6-24-50

County. Stafford  
KANSAS



CASING:  
8 5/8" 202' cem w/140 sx.

Elevation. \_\_\_\_\_

Production. dry

Figures Indicate Bottom of Formations.

soil, s and	35
sand	80
iron	83
shale, lime shells	202
red rock, shale	350
shale sdy, shells	390
sand	420
shale, shells	550
red rock	888
anhyd.	928
red rock, shale, salt	1310
shale, shells	1750
lime, shale	1800
lime	2030
lime, shale	2050
shale sdy, lime	2070
lime, shale	2225
lime	2330
lime, shale	2450
shale, shells	2660
lime, shale	2850
shale, shells	3065
lime, shale	3320
lime	3335
lime, shale	3673
lime	3930
lime, shale	4050
lime cherty, Miss.	
chert	4075
lime cherty	4080
lime, shale	4135
lime chert	4180
lime viola, chert	4192
lime, shale	4253
arbuckle	4272
Total depth	

Tops: Sample	
Heebner	3508
Brown lime	3658
Lansing white	3673
Mississippi	4048
Kinderhook	4080
Viola	4138
Simpson shale	4198
Arbuckle	4253