


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- WHITE EAGLE OIL COMPANY  
Farm- Abbott "A" No. 1

SEC. 25 T. 24 R. 11W  
SW NE NE

Total Depth. 4243  
Comm. 7-22-53 Comp. 8-5-53  
Shot or Treated.  
Contractor. Hilton Drlg Co., Inc.  
Issued. 12-5-53

County Stafford  
KANSAS



CASING:

8 5/8" 249' cem w/250 sx

Elevation. 1937 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

sand	41
sand, gravel, clay	120
shale	210
red bed	260
redbed, shale, shells	828
anhydrite	855
shale, shells	1530
lime brkn	1845
lime	2020
lime, shale	2175
lime	2240
shale, lime	2860
lime broken	3070
lime	3454
shale	3460
lime & shale	3684
lime	3877
lime, shale, chert	3976
lime, chert	4002
lime, shale, chert	4105
lime, chert	4146
lime, chert, shale	4169
shale Simpson	4177
lime Viola	4184
Shale Simpson	4222
lime Arbuckle	4243
Total Depth	

Tops: Sample- corrected by  
drilling time

Heebner	3454
Brown lime	3591
Lansing	3624
Pennsylvanian basal	
congl. shale	3938
chert congl. (possibly	
residual Miss. chert)	3952
Viola	4034
Simpson	4184
Arbuckle	4222

No Electric log was made of this test.

S.L.M. 3340=3339 (no correction applied)

Drill pipe was measured and tally board  
checked at 3700; measurements were found  
to be correct.

D.S.T. 3689-3702; open 1 hr, SI 20 min;  
recovered 165 feet salt water; 1220# BHP

Shows of Oil, G<sub>s</sub>, Water; none