

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- SHELL OIL CO.
Farm-H. A. Prescott No. 2

SEC. 25 T. 24 R. 14W

NE NW SE

330' fr NL 990' fr WL

County Stafford
KANSAS

Total Depth. 4230

PBSD 4210

Comm 6-16-53

Comp. 7-8-53

Shot or Treated.

Contractor.

Issued. 8-22-53

CASING:

8 5/8 832'

5 1/2 4229'

Elevation. 1943

Production. 10,014 BFPD, 11% W

Figures indicate Bottom of Formations.

surface & sand	40	TOPS:	
sand	190	Heebner	3425
shale & sand	350	Brown lime	3559
red bed & shale	820	Lansing KC	3591
anhydrite	845	Marmaton	3856
shale & shells	1065	Sooy	3907
shale, lime & sand	1260	Kinderhook	3927
shale & shells	1340	Viola	3986
shale & salt	1660	Simpson	4113
shale & shells	1730	Arbuckle	4153
lime & shale	3220		
lime	3300		
shale	3305		
lime	3319		
shale	3321		
lime & shale streaks	3361		
lime	3370		
lime & shale streaks	3425		
carbonaceous shale	3430		
lime & shale	3450		
lime	3471		
shale	3520		
shale & lime streaks	3542		
shale	3559		
lime	3564		
shale, sandy in part	3591		
lime	3603		
shale	3606		
lime & shale streaks	3613		
lime	3622		
lime & shale streaks	3630		
lime	3638		
lime & shale streaks	3660		
lime	3666		
lime & shale streaks	3675		
cherty lime	3686		
lime	3769		
shale	3776		
lime	3856		
shale	3868		
brown lime	3879		
shale	3883		
lime	3887		
shale	3907		
chert, limey in aprt	3927		
shale	3986		
chert	4005		
shale	4022		
chert	4113		
shale	4123		
sand	4133		
shale green & sand strks	4153		
dolomite	4230		
Total Depth P.B.	4210		