


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company-D. R. LAUCK OIL CO., INC.  
Farm- Youse No. 1

SEC. 26 T. 24 R.14W  
SW SW NW

Total Depth. 4270  
Comm. 11-16-55 Comp. 11-30-55  
Shot or Treated.  
Contractor.  
Issued. 1-14-56

County Stafford  
KANSAS



8 5/8 CASING:  
159' w/ 160 sx cmt.

Elevation. 1940 DF

Production. Dry

Figures indicate Bottom of Formations.

sand	120
shale & shells	159
blue shale	180
red bed & shells	335
sand	375
red bed	515
red bed, shale & shells	837
anhydrite	870
shale & shells	940
red bed, shale & shells	1185
salt & shale	1275
red bed & shale	1470
shale & shells	1720
shale & lime	1950
lime	2010
lime & shale	3604
lime	4041
lime & chert	4075
lime	4135
chert & lime	4155
lime	4185
lime & shale	4255
lime	4270
Total Depth	

TOPS:

Anhydrite	837
Heebner	3469
Brown lime	3604
Lansing	3636
Mississippian	3994
Viola	4069
Simpson shale	4182
Arbuckle	4231

DST #1: 3659-75, open 30 min. wk. bl.  
7 min. rec. 50' mud, BHP 840#/20 min.  
& still bldg.