


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. NATURAL GAS & OIL CO.
Farm. De Busk No. 1

SEC. 29 T. 24 R. 14W
SW SE NE

Total Depth. 4365
Comm. 9-1-54 Comp. 9-16-54
Shot or Treated.
Contractor. Natural Gas & Oil Co.
Issued. 10-16-54

County Stafford
KANSAS



CASING:
10 3/4 213' w/ 200 sx cmt.

Elevation. 1988 RB

Production. Dry

Figures Indicate Bottom of Formations. '

sand	155
shale & shells	350
red bed & shale	800
shale & shells	930
anhydrite	950
shale & shells	1645
shale & lime	3355
lime	3504
shale & lime	3675
shale	3694
lime	3953
lime & shale	4088
lime	4181
cherty lime & shale	4216
chert & lime	4263
lime & shale	4336
Arbuckle lime	4365
Total Depth	

TOPS:	
Anhydrite	930
Heebner	3552
Brown lime	3694
Lansing	3715
Mississippi	4095
Viola	4189
Simpson	4275
Arbuckle	4337

DST #1: 3738-62, open 1 hr. rec. 140'
SI&GC watery mud, SI 20 min. IFP &
FFP O#, BHP 1115#

DST #2: 3843-56, open 1 hr. strong
to weak blow 38 min. rec. 45' mud,
SI 20 min. IFP & FFP O#, BHP 630#

No schlumberger