


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM MANAGEMENT & HUDSON OIL CO.
Farm- Satterlee "B" No. 2

SEC. 31 T. 24 R. 14W
NE NW NW

Total Depth. 4402'
Comm. 10-14-57 Comp. 10-15-57
Shot or Treated.
Contractor. Transit Corp.
Issued. 9-19-59

County Stafford
KANSAS



CASING:

8 5/8" 250' cem w/200 sx.
5 1/2" 4397' cem w/150 sx.

Elevation. 2004' RB

Production. 96 BOPD

Figures indicate Bottom of Formations.

DRILLERS LOG NOT AVAILABLE

TOPS:

Heebner	3571
Toronto	3591
Douglas	3611
Brown Lime	3719
Lansing-Kansas City	3734
Base Kansas City	3973
Viola	4167
Simpson	4314
Arbuckle	4372

DST #1 3862-3872', op 1 hr, weak blow
thruout, rec. 40' slightly oil cut mud.
IBHP 1160#, FBHP 1240#.

DST #2 4370-4380', rec. 330' muddy oil
& oily water, with some water in bottom
60' only. IBHP 1295#, FBHP 1050#.

DST #3 4383-4395', rec. 30' oil cut
mud, with small quantity free oil in top
of tool. IBHP 1285#, FBHP 196#.

Total Depth 4402