


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STICKLE DRILLING CO. et al
Farm- Bowker No. 1

SEC. 36 T. 24 R. 14W
NW NE SE

Total Depth. 4325
Comm. 5-31-56 Comp. 6-12-56
Shot or Treated.
Contractor. Stickle Drilling Co.
Issued. 8-18-56

County Stafford
KANSAS



CASING:

8 5/8 202' w/ 200 sx cmt.

Elevation. 1949 DF

Production. Dry

Figures indicate Bottom of Formations.

sand	130
shale & clay	203
shale & shells	850
anhydrite	870
shale & shells	1740
lime & shale	2010
sandy lime	2120
lime & shale	2405
lime	2565
lime & shale	2890
broken lime	3025
lime & shale	3780
K. C. lime	3830
lime	3880
lime & shale	3950
Marmaton	4015
lime & shale	4095
Viola	4115
lime, shale & chert	4150
cherty lime & shale	4170
Viola chat	4182
chert & lime	4209
lime & shale	4250
Simpson sand & shale	4325
Total Depth	

TOPS:

Stone Corral Anhydrite	850
Heebner	3496
Brown lime	3638
Lansing	3666
Base K. C.	3940
Marmaton	3940
Conglomerate	4006
Viola	4064
Simpson	4234
Arbuckle	4296

DST #1: 4063-85, open 1 hr. good bl.
thruout, rec. 55' VSOCM, ICIP 845#/30
min. IFP 30#, FFP 50#, FCIP 100#/30
min.

DST #2: 4084-4115, open 1 hr. fair
bl. thruout. rec. 30' VSO specked mud,
ICIP 260#/30 min. IFP 30#, FFP 50#,
FCIP 65#/30 min.