

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Kachelman No. 4SEC. 36 T. 24 R. 14W
NE SW NW

Total Depth. 4213


Comm. 4-13-53

Comp. 5-1-53

Shot or Treated.

Contractor. Westgate Drilling Corporation

Issued. 6-13-53

County Stafford
KANSAS

CASING:
8 5/8 205' w/ 200 sx cement
5 1/2 set at 4212' w/ 150 sx cement

Elevation. 1948 DF

Production Temp. 25 BOPD

Figures Indicate Bottom of Formations.

sand	140
shale	203
shale & shells	205
shale, shells & red bed	459
shale & shells	855
anhydrite	880
shale & shells	1900
lime & shale	2055
lime	2230
lime & shale	3618
lime	3900
shale & lime	4011
lime & chert	4037
Viola	4156
shale	4163
Simpson shale	4170
Simpson sand	4180
Simpson shale	4198
Arbuckle lime	4213
Total Depth	

TOPS:

Anhydrite	853
Heebner	3450
Lansing	3615
Base KC	3884
Cherty Conglomerate	3948
Viola	4016
Simpson	4154
Arbuckle	4195

DST #1: 4170-80, open 1 hr. rec. 5'
mud, BHP 940#DST #2: 4197-4208, open 1 hr. rec.
515' gas, 2365' oil, BHP 1350#

Ran Schlumberger

Perf. 67 holes 4196-4210 1/2, FU 2000'
oil in 3 hrs: SWBD. 15 BOPH for 4
hrs. natural, no water.
Filed 25 BOPD Temp. Prod. Affid.