


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEBEN DRG., INC. & RUSSELL COBB, JR.
Farm- Curtis No. 1

SEC. 2 T. 24 R. 11W
SW SW NE

Total Depth. 4210'
Comm. 6-10-56 Comp. 6-24-56
Shot or Treated.
Contractor. Leben Drlg. Inc.
Issued. 8-4-56

County Stafford
KANSAS



CASING:
8" 201'

Elevation. 1057 BB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	35
sand	179
shale	200
shale-shells	295
sand	380
shale-shells	620
shale	860
Anhydrite	885
shale-lime	955
shale-shells	1511
shale-lime	1815
lime	1926
shale-lime	2016
lime	2245
shale-lime	3660
lime	4106
chirt-lime	4123
shale-lime	4160
lime	4210 RTD
Total Depth	

TOPS:

(All tops corr. to Elec. Log)
(Elevation 1957 KB)

Heebner shale	3468
Brwn lime	3607
Lansing	3628
B/Kansas City	3880
Conglomerate(shaly)	3964
Viola	4005
Simpson	4129
Arbuckle	4182

DST #1 3648-3660 Open 1 hr.,
weak steady blow, rec.
45' GCM, BHP 0# in 20
min.

DST #2 3690-3702 Open 1 hr.,
fair blow, rec. 195'
muddy wtr, BHP 1180#
in 20 min.

DST #3 3778-3805 Open 30 mins.,
weak blow dead in 7 min.,
rec. 25' mud, BHP 1240#
in 20 min.

DST #4 3953-4000 Open 1 hr.,
strong steady blow, Rec.
2520' gas, 60' of slightly
OCM & 150' of heavily oil
& GCM, BHP 290# in 20 min.

DST #5 4001-4020 Open 30 min,
weak blow for 8 min., rec.
25' mud, BHP 0# in 20 min.