

GREAT LAKES CARBON CORP.
Eldred No. 1.

SEC. 8
NE SW SW


T. 24 R. 14 W

59242

Drake

Total Depth. 4270'
Comm. 8-31-43 Comp. 9-30-43
Shot or Treated.
Contractor. Crow Drlg. Co.
Issued. 10-23-43

County. Stafford



CASING:
8 5/8" 909' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

clay	75	Geological Data (Tops)	
sand	158	Anhydrite	928
shale	188	Topeka	3200
shale & shells	335	Lansing	3678
red rock	550	Chert Congl.	4030
anhydrite shale	628	Viola Chert	4103
red rock & shells	925	Weathered Simp.	4175
shale	927	Arbuckle	4220
lime & shale	975		
shale & shells	1483		
shale & salt	1664		
shale & lime	1864		
lime	1877		
lime & shale	1930		
lime	2198		
lime sdy	2231		
lime	2308		
lime & shale	2358		
lime brkn	2423		
lime	2495		
lime & shale	2593		
lime	2660		
lime & shale	2710		
lime brkn & shale	2766		
lime & shale	2838		
chert lime	2858		
lime & shale	2970		
shale & chert	2988		
lime	3063		
lime brkn	3179		
lime & shale	3263		
lime brkn	3306		
shale & lime	3353		
lime brkn	3380		
lime	3390		
lime brkn	3521		
lime	3560		
shale & lime	3653		
lime	3693		
lime & shale	3719		
lime	3801		
lime sft	3810		
lime	3816		
lime brkn	3864		
lime	3944		
lime & shells	3981		
lime	4032		
lime & chert	4035		
lime	4051		
chert lime	4061		
lime	4089		
chert lime	4158		
lime	4181		
shale & lime	4221		
lime	4270		
Total Depth.			