


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - JOHN LINDAS OIL, INC. ETAL
Farm - Koelsch No. 1

SEC. 10 T. 24 R. 14W
SE NE SE

Total Depth. 4243
Comm. 2-16-50 Comp. 3-5-50
Shot or Treated. 1000 acid
Contractor. Lindas Oil, Inc.
Issued. 4-22-50

County. Stafford
KANSAS



CASING:
8 5/8" 222' cem w/150 sx.
5 1/2" 4240'

Elevation. _____

Production. Pot. 252 bbls / no water

Figures Indicate Bottom of Formations.

soil, clay	15
sand	165
shale	260
red bed	355
sand	415
red bed, shells	660
sand	710
red bed, shells	855
anhydrite	882
red bed, shale	1200
shale	1245
salt, shale	1515
shale, shells	1730
lime, shale	2110
lime, shale strks	2220
lime	2285
lime brkn, shale	2430
lime, shale	2700
lime brkn, shale	3220
lime	3575
lime brkn	3608
lime	3895
lime, shale	3925
lime	3968
shale	4005
lime, shale, chert	4025
lime cherty, shale	4055
lime	4080
lime, chert shale	4128
lime, chert	4152
lime	4200
shale, dolo, cherty	4219
lime, chert	4243
Total depth	

Tops: Scout	
Topeka	3320
Kansas City	3634
Conglomerate	3988
Kinderhook	4013
Viola	4028
Simpson	4158
Arbuckle	4213