


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUNRAY OIL
Farm- Davis No. 1

SEC. 11 T. 24 R. 14W
SW SW NW

Total Depth. 4026
Comm. 10-3-51 Comp. 10-18-51
Shot or Treated.
Contractor. R. W. Rine Drlg. Co.
Issued. 12-29-51

County Stafford
KANSAS



CASING:

8 5/8" 443' cem w/350 sxs.
5 1/2" 4026' cem w/150 sxs.

Elevation. 1957

Production. Phy. Pot. 20 BO &
5% wtr.

Figures Indicate Bottom of Formations.

sand, clay	200
red rock, shells	450
red clay, shells,	
sand	1090
sand, shale, shells	1525
salt, shells	1725
shale, shells	1825
lime	2045
lime, shale	2150
lime	2280
lime, shale	2505
sand, shale	2665
sandy shale	2755
shale	3010
shale, lime	3270
lime	3530
lime, shale	3635
lime	3730
lime, sand, shale	3777
lime	3975
lime, chert	4026
Total depth	

Tops:	
Heebner shale	3484
Brown lime	3618
Lansing	3645
Cherty Marmaton	3918
Conglomerate	4004
Viola	4022

DST 3763-77 open 1 hr. rec.
148' muddy oil, 2' wtr.,
BHP 242# FP 111#; DST 3808-17
open 1 hr. rec. 62' wtr.,
BHP 1420#;
CO 3933; lanc well log; 16/3768-72;
1600 A; 5-6 BOPH no lime.
Phy Pot. 20 BOPD 7 5% wtr.