

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

60299 ✓

Company - FALCON SEABOARD DRIG.CO.  
Farm - J.C.Koelsch No. 1.


SEC. 11 T. 24 R. 14 W  
NW SW SW

DISCOVERY WELL

Total Depth. 4258'  
Comm. 3-29-44  
Shot or Treated.  
Contractor.  
Issued. 8-26-44

Comp. 5-24-44

County. Stafford  
KANSAS



CASING:

10 3/4" 407' Cem.  
5 1/2" 4143' Cem.

Elevation. \_\_\_\_\_

Production. Pot.254 B.

Figures Indicate Bottom of Formations.

surface clay & sand	200	Tops:	
sand & shale	250	Lansing	3628
shale & red bed	340	Viola	3998
sand	380	Simpson	4168
shale	415	Arbuckle	4205
shale & shells	470		
red bed	700		
shale & red bed	800		
red bed & sand	848		
anhydrite	935		
shale & shells	1075		
shale	1175		
shale & shells	1480		
shale & lime	1560		
shale & shells	1735		
lime	1805		
shale & lime	1925		
lime	1995		
lime cherty	2030		
lime	2100		
lime & shale	3025		
lime	3030		
shale & lime	3065		
shale	3085		
shale & lime	3280		
shale	3295		
shale & lime	3335		
lime	3530		
shale & lime	3635		
lime	3890		
shale	3920		
lime & shale	3990		
lime	4015		
conglomerate	4095		
chert	4120		
conglomerate	4139		
chert rough	4145		
chert	4155		
lime	4170		
lime & dolomite	4178		
shale	4205		
lime cherty	4230		
lime	4258		
Total Depth.			