


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 508 E. Murdock, Wichita, Kansas

Company - ATLANTIC REFG.
 Farm - Shell No. 2

SEC. 13 T. 24 R. 14W
 NW NE NW

Total Depth. 3845
 Comm. 3-10-50 Comp. 3-28-50
 Shot or Treated.
 Contractor. Holm Louis Drlg. & Flournoy Drlg.
 Issued. 4-29-50

County. Stafford
 KANSAS



CASING:

8 5/8" 899.30' cem. w/500 sx.
 5 1/2" 3835.20' cem. w/250 sx.

Elevation. _____

Production. 80 BOPD

Figures Indicate Bottom of Formations.

shale & shells	290
sand & shale	360
shale	450
red bed	500
shale & lime shells	809
anhyd.	824
shale & lime shells	912
shale & shells	1680
lime & shale	1790
lime	1805
lime & shale	1830
lime	1890
lime & shale	2415
shale & lime	2605
shale & lime shells	2760
lime & shale	3340
lime	3520
shale & lime	3595
lime	3845
Total Depth	

Tops:
 Lansing 3580

Perforated 3651 to 3661 w/64 jet holes.

Swabbed 3 FOPH 5% salt. wtr.

Producing area 3651-3661