

KANSAS DRILLERS LOG

S. 27 T. 24 R. 15 ^N/_W

Loc. C E 1/2 NW

County Stafford

API No. 15 — 185 — 20,490
County Number

Operator
F. G. Holl & Sterling Drilling Co.

Address 6427 East Kellogg
Wichita, Kansas


Well No. #1 Lease Name
Campbell

Footage Location
660 feet from (N) (S) line 330 feet from (E) (W) line

Principal Contractor Geologist
Sterling Drilling Co. Bill Shepherd

Spud Date Total Depth P.B.T.D.
1-31-74 4256

Date Completed Oil Purchaser
2-8-74



Locate well correctly

Elev.: Gr. 2027

DF 2033 KB 2036

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8 5/8	28	251	50/50 Pozmix	225	2% gel, 3% cc
Production		4 1/2	9.5	4255	Pozmix	100	Salt saturated 1/2# Floseal, tuffner, & gilsonite.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			12	.	4199-4205
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
FRAC 500 BW + 12000#SD.	

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.) Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas 1,250 MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator F. G. HOLL

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1

Lease Name CAMPBELL

GAS

S 27 T 24 R 15 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
NO DST'S			Heebner	3642 -1606
WELEX RAD-GUARD-CALIPER			Br. Lm.	3788 -1752
			Lansing	3796 -1760
			Miss.	4180 -2144
			Kind Sd.	4196 -2160
			TD	4256 -2220

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Elwyn H. Boger
Signature

Geologist
Title

4-1-77
Date

Date

27-24S-15W
C-E/2 NW

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

API # 15-185-20490
KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas



WELL LOG ----- CAMPBELL #1
Located: C E/2 NW, Section 27-24S-15W, Stafford County, Kansas

OWNER: F. G. Holl and Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

ELEVATION: 2036 KB

COMMENCED: January 31, 1974
COMPLETED: February 8, 1974

LOG TOPS:	DEPTH:
Heeb	3642
Br Lm	3788
Lans	3796
Miss	4180
Kind Sd	4196
TD	4256

TOTAL DEPTH: 4256'

LOG

CASING RECORD

- 0 - 147 Sand and Clay
- 147 - 150 Red Bed
- 150 - 255 Shale
- 255 - 1150 Shale, Lime Stks.
- 1150 - 1840 Shale and Shells
- 1840 - 3758 Lime and Shale
- 3758 - 4240 Lime
- 4240 - 4256 Lime and Shale

Ran 6 joints 8 5/8" 28# pipe, 242.36' set at 251.36 K.B. Cemented with 225 sacks 50/50 Poxmix, 2% gal, 3% cc. Plug down at 7:25 PM, 1-21-74.

Ran 137 joints 4 1/2" 9.5# used casing, 4260.35', threads off, set at 4255' with 100 sacks salt saturated Poxmic, 1/4# Floseal, tuffner and gilsonite added with 500 gals. mudflush ahead. Plug down at 3:10 AM, 2-8-74.

