

2-24-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- WESTGATE-GREENLAND OIL CO.
Farm- Munz No. 1

SEC. 2 T. 24 R. 15W
SE SE SE

Total Depth. 4155
Comm. 6-18-52 Comp. 7-3-52
Shot or Treated.
Contractor. Jackson Drlg. Corp.
Issued. 7-26-52

County Stafford
KANSAS



CASING:

10 3/4" 200' cem. w/225 sx

Elevation. 2005 LF

Production. Dry

Figures indicate Bottom of Formations.

sand, clay	40
sand & shale	100
shale & shells	200
shale	300
red bed & shale	425
sand	475
red bed, shale	913
anhydrite	940
shale & shells	1770
lime & shale	1930
lime	2185
lime & shale	3150
lime	3520
H. shale	3524
lime & shale	3650
lime	3915
lime & shale	3961
conglomerate	4020
chert & lime	4066
chert	4083
simpson shale	4095
shale, sand	4115
arbuckle lime	4155
Total Depth	

Tops:

Anhydrite	913
Hecbner	3513
Toronto	3536
Brown Lime	3649
Lansing	3657
Viola	4015
Simpson	4060
Arbuckle	4113 4118 Elev log

Schlumberger run.

DST: 4114-23' open 1 hr.
rec. 1150' sulphur water,
BHP 1260# FC 570#.