


STANOLIND OIL & GAS CO.  
W. Nagel No. 3.

SEC.3 T.24 R. 15 W  
CEL NW SW  
1980'N SL 990'E WL SW $\frac{1}{4}$   
County. Stafford

Total Depth. 4150'  
Comm. 10-3-41 Comp. 11-5-41  
Shot or Treated.  
Contractor.  
Issued. 11-29-41 Rotary O-4150



CASING:  
8 5/8" 270' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	6'5"
clay & sand	130
sand	180
shale & stks sand	240
shale	280
red bed	425
sand & shale	715
red bed & shale	943
anhydrite	970
shale & shells	1345
shale & lime	1490
salt, shale, shells	1765
lime, stks shale	1897
shale & lime	2003
lime brkn	2098
lime	2164
lime brkn	2448
lime, stks shale	2551
lime brkn	2580
shale & shells	2682
lime & shale	2698
lime, shells, shale	2758
shale & lime	2900
lime	3564
shale	3617
shale & lime	3650
lime K.C.	3696
lime	3890
lime brkn	3923
lime & shale	3995
shale & chert	4001
chert, lime	4020
shale & chert	4045
lime cherty	4074
chert	4085
shale	4100
shale & lime	4131
lime	4150
Total Depth.	

Lansing 3650-4006  
Viola 4006-4095  
Simpson 4095-4131  
Arbuckle 4131-4150