


CITIES SERVICE OIL CO.
Walker No. 1.

SEC.10 T.24 R.15 W
NEc SE
330'S 330'W of E $\frac{1}{2}$ Cor.

10-24-15W
County. Stafford



Total Depth. 4160'
Comm. 9-24-42 Comp. 10-15-42
Shot or Treated. None
Contracter. Corbett-Barbour Drlg.Co.
Issued. 11-21-42

CASING:
8 5/8" 202' Cen.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand	0-80	10-10-42 Halliburton drill
shale & shells	202	stem test, 4022-33, made
shale,sand,shells	790	800' mud, no oil, in 45
shale & shells	1410	minutes.
salt	1485	10-12-42 Halliburton drill
shale & shells	1800	stem test 4045-54, est.
lime	1830	100,000 cu ft sour gas &
anhydrite	1965	75' mud in 45 minutes.
lime	2070	
lime brkn	2280	
lime	2540	
lime & shale	2675	
shale & lime	2780	
lime brkn & shale	2900	
shale & lime	2975	
shale & shells	3100	
lime	3240	
lime brkn	3290	
lime brkn & shale	3390	
lime	3580	
shale & lime	3605	
shale	3612	
lime	3665	
lime & shale	3715	
lime	3786	
cored lime(rec.1 $\frac{1}{2}$ ')	3796	
lime	3930	
shale	3970	
shale & lime	3981	
conglomerate	3984	
chert	4014	
shale	4025	
sand	4027	
cored sand & shale		
(rec.6')	4033	
shale	4045	
cored lime(rec.4 $\frac{1}{2}$ ')	4050	
cored lime(no rec.)	4054	
cored sand & shale		
(rec.3')	4060	
shale	4062	
cored shale(rec.3')	4068	
lime & chert	4083	
shale	4088	
cored shale(rec.3')	4094	
shale & chert	4107	
lime & chert	4160	
Total Depth.		

Tops: Lansing	3612
Viola	3984
Simpson	4014
Arbuckle	4044
Penetration	116'