

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


11-24-15W

Company- WILKINSON DRILLING, INC.  
Farm- Harkness No. 2

SEC. 11 T. 24 R. 15W  
C W/2 W/2 NW

Total Depth. 4170'  
Comm. 11-17-60 Comp. 11-29-60  
Shot or Treated.  
Contractor.  
Issued. 5-27-61

County Stafford  
KANSAS



CASING:  
8 5/8" 228' cem w/185 sx.  
4" 4169'

Elevation. 2031' KB

Production. 150 BOPD

Figures indicate Bottom of Formations.

shale & shells	230
red beds & shale	491
shale, shells & red beds	940
Anhydrite	960
shale & shells	1300
shale & lime	1910
lime & shale	3482
Heebner shale	3490
lime	3494
shale	3504
lime & shale	3522
shale & silt	3620
lime & shale streaks	3926
vari colored shale & chert	3986
chert	4016
shale	4026
sand	4032
shale	4043
sand & shale	4052
Arbuckle	4170 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite	940
Heebner	3482
Toronto	3503
Douglas	3522
Brown Lime	3620
Lansing	3629
Viola	3987
Arbuckle	4053