


HAVE LOG

KANSAS CORPORATION COMMISSION

WELL RECORD

3-24-15W

(Mail to Kansas Geological Survey, 4150 Monroe Street, Wichita, Kansas 67209)



Lease Name: Cornwell Well No. 1
 Well Located: Stafford County
S/2 SE NW SEC 3 TWP 24S RGE 15W
 Operator: Halliburton Oil Producing Company
 Address: 117 Cameron Bldg., Oklahoma City, Oklahoma
 Elevation: Ground 2020 D.F. 2023 K.B. 2025
 Type Well: (Oil, gas, dry hole) Gas

Drilling Commenced: 11-16 19 71 Drilling Completed: 11-21 19 71
 Well Completed: 12-31 19 71 Total Depth 3102
 Initial Production: 3,200 MCFD

Casing Record

Size: 8 5/8 Set at 252' Size: Set at
 Size: 4 1/2 Set at 3101' Size: Set at

Liner Record

Size: None Set from To

Cementing

Casing Size	Sacks	Type Cement and Additives
<u>8 5/8</u>	<u>200</u>	<u>Pozmix</u>
<u>4 1/2</u>	<u>100</u>	<u>Pozmix</u>

Perforations

Formation	Perforated Interval and Number Shots
<u>Howard</u>	<u>3028-34, 3068-71, 36 holes</u>

Electric Log Run (Show type log and depths covered)

RA Log 252-3090'

3-34-12.5

Formation Top Bottom

Show Drill Stem Tests,
Well Stimulation and
Production Tests

3-24-15w

Herrington	1992	2106
Winfield	2048	2058
Towanda	2108	
Ft. Riley	2150	2230
Wreford	2300	
Council Grove	2370	2376
Cottonwood	2477	
Neva	2514	2524
Red Eagle	2581	2608
Foraker	2648	
Admire	2708	
Wabaunsee	2767	
Tarkio	2894	2934
Elmont	3003	3008
Howard	3026	3073

DST 2564-2605. Recovered 70' mud

DST 3104-3090 Gas to surface in 2½ mins.

~~XX~~

Flow 800 MCFD after 40 min.

FP 126-233 SIP 947-938



Company;
Farm;
Location;
Section;
County;
Contractor;
Comm;
Compl;
Total Depth;
Casing;

November 22, 1971

Halliburton Oil Producing Company
#1 Cornwell
C S/2 SE NW
3-24-15W
Stafford
Woodman & Iannitti Drilling Co.
November 15, 1971
November 21, 1971
3100'
8 5/8" @ 252' w/200 sx.
4 1/2" @ 3099' w/200 sx.

Figures Indicate Bottom Of Formations:

85	Sand
252	Shale
290	Shale
325	Sand & Shale
450	Red Bed & Shale
530	Sand
700	Shale & Red
946	Red Bed & Shale
1325	Red Bed
1810	Shale & Shells
1960	Lime & Shale
2080	Lime & Shale
2215	Lime & Shale
2330	Lime & Shale
2480	Lime & Shale
2605	Lime & Shale
2635	Lime & Shale
2840	Lime & Shale
3020	Lime & Shale
3090	Lime & Shale
3100	Total Depth