


STANOLIND OIL & GAS CO.
 H.F. Corrwoll "B" No. 1.

SEC. 3 T. 24 R. 15W
 CW $\frac{1}{2}$ SE NW
 660' N SL 1650' E WL NW $\frac{1}{4}$

Total Depth. 4007'
 Comm. 9-9-41 Comp. 9-27-41
 Shot or Treated.
 Contractor.
 Issued. 10-25-41 Rotary O-4007

County. Stafford



CASING:
 8 5/8" 276' 0" Com.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	5' 6"
sand	150
shale & stks sand	230
shale	286
red bed	440
sand	490
red bed & shells	947
anhydrite	988
red bed & shale	1017
shale & shells	1425
shale, shells, salt	1528
shale & shells	1660
shale	1805
anhydrite & stks	
shale	1935
lime & stks shale	2505
shale & shells	2732
shale & lime	2819
shale	2900
lime brkn	2920
lime & shale	2963
lime	2972
lime brkn	2990
shale & lime	3151
lime	3191
shale & lime	3283
shale	3300
lime	3362
lime, stks shale	3471
lime	3572
lime, shale	3605
lime	3618
shale sticky	3636
lime	3721
lime cherty	3738
lime Lansing	3758
lime	3876
lime & shale	3974
lime & chert	3996
lime	4007
Total Depth.	

Lansing 3633-3974
 Viola 3974-4007