

3-24-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SAM WALLINGFORD
Farm. Cornwell No. 2

SEC. 3 T. 24 R. 15W
SW SW NW

Total Depth. 4133'
Comm. 12-8-61 Comp. 12-18-61
Shot or Treated.
Contractor. S & S Drlg.
Issued. 6-16-62

County Stafford
KANSAS



CASING:
8" 300'
5" 4132'

Elevation. 2023' DF

Production. 1,798,000 CFG

Figures Indicate Bottom of Formations.

surface clay	30
sand	135
red bed & shale	150
gray shale	301
red bed & shale	940
Anhydrite	970
red bed, shale & shells	1125
shale & shells	1825
lime	2235
lime & shale	2400
shale	2535
shale & lime	2770
lime & shells	2970
shale & lime	3180
shale & shells	3310
lime & shale	3445
lime	3462
lime & shale	3630
lime	2945
shale, lime & chert	4085
shell lime	4125
Arbuckle lime	4133
Total Depth	

TOPS:	
Heebner	3502
Toronto	3528
Brown Lime	3643
Kansas City	3650
Base Kansas City	3895
Viola	3988
Simpson	4085
Arbuckle	4126