

34-24-15W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company - J. A. DAVIS & J. H. CHILD ET AL
Farm Young No. 1

SEC. 34 T. 24 R. 15W
SW NE SE

Total Depth. 4432'
Comm 3-25-48 Comp. 4-19-48
Shot or Treated.
Contractor Sterling Drilling Company
issued 5-8-48

County. Stafford
KANSAS



Elevation. 2022 Ind.

Production. Dry

Figures indicate Bottom of Formations.

clay & sand	0-135
shale & shells	285
shale, shells & red bed	400
red bed & sand	650
sand	810
red bed & shale	955
anhydrite	975
shale & shells	1025
red bed	1155
red bed, shale & shells	1480
salt	1575
shale & shells	1835
shale & lime	2070
lime	2200
shale & lime	3240
lime	3320
lime & shale	3393
lime	3690
shale & lime	3745
lime	4049
shale	4058
shale & lime	4155
shale	4164
lime	4186
lime & chert	4243
lime	4270
lime cherty	4285
lime & chert	4302
lime	4329
Simpson	4416
Arbuckle lime RTD	4420
Arbuckle lime	4432
Total Depth	

Tops: (Corr. to D.F.)

Cim. Anhydrite	955
Topeka, Brwn Lime	3745
Lansing-K.C.	3754
Miss. Lime	4168
Kinderhook	4194
Misener	4311
Simpson	4327
Arbuckle	4415