


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

STANOLIND OIL & GAS CO.
Walter Nagel No. 2.

SEC.3 T.24 R.15W
CW $\frac{1}{2}$ NE SW
1980'N SL 1650'E WL SW $\frac{1}{4}$

Total Depth. 4126' PB3827'
Comm. 8-4-41 Comp. 8-27-41
Shot or Treated.
Contractor.
Issued. 10-25-41 Rotary O-4126

County. Stafford



CASING:
8 5/8" 264'8" Cem.
4 1/2" 3811'2" Cem.

Elevation.

Production. Pot. 39,652 BO,
no wtr, Drawdown

Figures Indicate Bottom of Formations.

cellar	6'6"
clay & sand	90
shale	276
red bed	370
sand	420
red bed & shale	830
shale red & blue	942
anhydrite	965
shale & shells	1620
shale & salt	1770
lime & shale	1840
anhydrite	1975
lime & shale	2205
limo	2250
lime & shale	2575
shale	2600
shale & shells	2800
shale	2860
lime brkn	2890
lime & shale	3338
lime	3435
lime & shale	3468
limo	3497
lime & shale	3567
shale	3624
lime	3775
lime & chert	3785
lime	3833
lime & shale	3964
lime	3967
lime & chert	3985
chert	4006
chert & lime	4028
chert	4043
Simpson shale & sand	4052
shale	4074
shale & lime	4085
lime	4126
Total Depth.	

Plugged back w/cement 3827

Lansing lime 3620-3962
Viola chert 3962-4043
Simpson lime 4043-4083
Arbuckle 4083-4126

Blew load wtr & tools out
of hole & flowed 95 Bbls
in 15 minutes - flowing
test thru 1" choke - 1st
hr 72 bbls - 2nd hr 58
bbls, no wtr. Drawdown
Pot. 39,652 BO, no wtr
Production during entire
test 217 BO in 16 hrs.